
Somy's Place

Bumper Boats & Mini Golf Expansion 349 Main Street Somers, Connecticut 06071 Map 05 Lot 12 Zone: A-1



KEY PLAN MAP

1"=500"

Applicant/Owner


Driving Range 349 Main Street, LLC
15 Mullen Road
Enfield, CT 06082

Prepared By

J.R. Russo & Associates, LLC
P.O. Box 938
East Windsor, CT 06088
860-623-0569


DRAWING INDEX


HEET TITLE	SHEET NO.	LATEST REVISION
<u>VIL</u>		
OVER SHEET · · · · · · · · · · · · · · · · · ·	····1 of 9	9-29-21
VERALL LAYOUT PLAN · · · · · · · · · · · · · · · · · · ·	····2 of 9	9-29-21
EMOLITION PLAN · · · · · · · · · · · · · · · · · · ·		9-29-21
TE PLAN (20 SCALE)····································	····4 of 9	9-29-21
TE PLAN (20 SCALE)····································	····5 of 9	9-29-21
TE PLAN (20 SCALE)····································	····6 of 9	9-29-21
ONSTRUCTION NOTES & DETAILS	····7 of 9	9-29-21
ETAILS	··· 8 of 9	9-29-21
ETAILS	· · · 9 of 9	9-29-21



Proposed Paves Spaces (includes 8 ADA spaces)

=318 spaces







BY: LF/TAC CHK: JEU

REVISIONS

<u>DATE</u> 9-29-21 <u>SCALE</u> 1"=20' JOB NUMBER 2007-081 SHEET 4 of 9

Site Plan





Site Preparation

Grade in accordance with the Land Grading measure which is in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.

Install all necessary surface water controls.

For areas to be moved remove all surface stones 2 inches or larger. Remove all other debris such as wire, cable tree roots. pieces of concrete, clods, lumps, or other unsuitable material.

Lawn Areas: Premium Seed Mix for Sun and Shade.

Apply topsoil, if necessary, in accordance with the Topsoilina measure which is in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.

Apply ground limestone and fertilizer according to soil test recommendations (such as those offered by the University of Connecticut Soil Testing Laboratory or other reliable source).

Where soil testing is not feasible on small or variable sites, or where timing is critical, fertilizer may be applied at the rate of 300 pounds per acre or 7.5 pounds per 1,000 square feet of 10-10-10 or equivalent and limestone at 4 tons per acre or 200 pounds per 1,000 square feet.

Work lime and fertilizer into the soil to a depth of 3 to 4 inches with a disc or other suitable equipment.

Inspect seedbed just before seeding. If the soil is compacted, crusted or hardened, scarify the area prior to seeding.

Seed Application

Apply selected seed at rates per manufacturer's recommendations uniformly by hand, cyclone seeder, drill, cultipacker type seeder or hydroseeder (slurry including seed, fertilizer). Normal seeding depth is from 0.25 to 0.5 inch. Increase seeding rates by 10% when hydroseeding or frost crack seeding. Seed warm season grasses during the spring period

See guidelines in the Mulch For Seed measures.

MAINTENANCE

Inspect temporary soil protection area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or greater during the first growing season.

Where seed has been moved or where soil erosion has occurred, determine the cause of the failure and repair as needed.

TEMPORARY SEEDING (TS)

SPECIFICATIONS Site Preparation

Install needed erosion control measures such as diversions. grade stabilization structures, sedimentation basins and grassed waterways in accordance with the approved plan.

Grade according to plans and allow for the use of appropriate equipment for seedbed preparation, seeding, mulch application and mulch anchoring.

Seedbed Preparation

Loosen the soil to a depth of 3—4 inches with a slightly roughened surface. If the area has been recently loosened or disturbed, no further roughening is required. Soil preparation can be accomplished by tracking with a bulldozer, discing harrowing, raking or dragging with a section of chain link fence.

Apply ground limestone and fertilizer according to soil test recommendations (such as those offered by the University of Connecticut Soil Testing Laboratory or other reliable source).

If soil testing is not feasible on small or variable sites, or where timing is critical, fertilizer may be applied at the rate of 300 pounds per acre or 7.5 pounds per 1,000 square feet of 10-10-10 or equivalent.

Apply seed uniformly by hand, cyclone seeder, drill, cultipacker type seeder or hydroseeder. The temporary seed shall be Rye (grain) applied at a rate of 120 pounds per acre. Increase seeding rates by 10% when hydroseeding.

See guidelines in the Mulch For Seed measures.

MAINTENANCE

Inspect temporary seeding area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or greater for seed and mulch movement and rill erosion.

Where seed has been moved or where soil erosion has occurred, determine the cause of the failure and repair as needed.

MULCH FOR SEED (MS)

SPECIFICATIONS

Types of Mulches within this specification include, but are not limited to:

1. Hay: The dried stems and leafy parts of plants cut and harvested, such as alfalfa, clovers, other forage legumes and the finer stemmed, leafy grasses. The average stem length should not be less than 4 inches. Hay that can be windblown should be anchored to hold it in place.

2. Straw: Cut and dried stems of herbaceous plants, such as wheat, barley, cereal rye, or brome. The average stem length should not be less than 4 inches. Straw that can be windblown should be anchored to hold it in place.

3. Cellulose Fiber: Fiber origin is either virgin wood, post-industrial/pre-consumer wood or post consumer wood complying with materials specification (collectively referred to as "wood fiber"), newspaper, kraft paper, cardboard (collectively referred to as "paper fiber") or a combination of wood and paper fiber. Paper fiber, in particular, shall not contain boron, which inhibits seed germination. The cellulose fiber must be manufactured in such a manner that after the addition to and agitation in slurry tanks with water, the fibers in the slurry become uniformly suspended to form a homogeneous product. Subsequent to hydraulic spraying on the ground, the mulch shall allow for the absorption and percolation of moisture and shall not form a tough crust such that it interferes with seed germination or growth. Generally applied with tackifier and fertilizer. Refer to manufacturer's specifications for application rates needed to attain 80%-95% coverage without interfering with seed germination or plant growth. Not recommended as a mulch for use when seeding occurs outside of the recommended seeding dates.

Tackifiers within this specification include, but are not limited to: Water soluble materials that cause mulch particles to adhere to one another, generally consisting of either a natural vegetable gum blended with gelling and hardening agents or a blend of hydrophilic polymers, resins, viscosifiers, sticking aids and gums. Good for areas intended to be moved. Cellulose fiber mulch may be applied as a tackifier to other mulches, provided the application is sufficient to cause the other mulches to adhere to one another. Emulsified asphalts are specifically prohibited for use as tackifiers due to their potential for causing water pollution following its

Nettings within this specification include, but are not limited to: Prefabricated openwork fabrics made of cellulose cords, ropes, threads, or biodegradable synthetic material that is woven, knotted or molded in such a manner that it holds mulch in place until vegetation growth is sufficient to stabilize the soil. Generally used in areas where no mowing is planned.

Grade according to plans and allow for the use of appropriate equipment for seedbed preparation, seeding, mulch application and mulch anchoring.

Timing: Applied immediately following seeding. Some cellulose fiber may be applied with seed to assist in marking where seed has been sprayed, but expect to apply a second application of cellulose fiber to meet the requirements of Mulch For Seed in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.

Spreading: Mulch material shall be spread uniformly by hand o machine resulting in 80%-95% coverage of the disturbed soil when seeding within the recommended seeding dates. Applications that are uneven can result in excessive mulch smothering the germinating seeds. For hay or straw anticipate an application rate of 2 tons per acre. For cellulose fiber follow manufacture's recommended application rates to provided 80%-95% coverage.

When seeding outside the recommended seeding dates, increase mulch application rate to provide between 95%-100% coverage of the disturbed soil. For hay or straw anticipate an application rate to 2.5 to 3 tons per acre.

When spreading hay mulch by hand, divide the area to be mulched into approximately 1,000 square feet and place 1.5-2 bales of hav in each section to facilitate uniform distribution.

For cellulose fiber mulch, expect several spray passes to attain adequate coverage, to eliminate shadowing, and to avoid

Anchoring: Expect the need for mulch anchoring along the shoulders of actively traveled roads, hill tops and long open slopes not protected by wind breaks.

When using netting, the most critical aspect is to ensure that the netting maintains substantial contact with the underlying mulch and the mulch, in turn, maintains continuos contact with the soil surface. Without such contact, the material is useless and erosion can be expected to occur.

MAINTENANCE

Inspect mulch for seed area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or greater until the grass has germinated to determine maintenance needs.

Where mulch has been moved or where soil erosion has occurred, determine the cause of the failure and repair as needed.


SOIL ERSOION & SEDIMENT CONTROL NOTES

- 1. The contractor/developer shall notify the Town Engineer and/or the IWWA Agent at least two working days before the following:
 - 1. Start of construction 2. Completion of clearing limit demarcation
 - 3. Installation of E&S measures
 - 4. Completion of site clearing 5. Completion of rough grading

 - 6. Completion of final grading


 - 7. Close of construction season 8. Completion of final landscaping
- 9. Prior to the removal of construction E&S control measures 2. All soil erosion and sediment control work shall be done in strict
- accordance with the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition. 3. Any additional erosion/sediment control deemed necessary by the
- engineer during construction, shall be installed by the developer. In addition, the developer shall be responsible for the repair/replacement and/or maintenance of all erosion control measures until all disturbed areas are stabilized to the satisfaction
- 4. All soil erosion and sediment control operations shall be in place prior to any grading operations and installation of proposed structures or utilities and shall be left in place until construction is completed and/or area is stabilized.
- 5. In all areas, removal of trees, bushes and other vegetation as well as disturbance of the soil is to be kept to an absolute minimum while allowing proper development of the site. During construction, expose as small an area of soil as possible for as short a time as
- 6. The developer shall practice effective dust control per the soil conservation service handbook during construction and until all areas are stabilized or surface treated. The developer shall be responsible for the cleaning of nearby streets, as ordered by the town, of any debris from these construction activities.
- 7. All fill areas shall be compacted sufficiently for their intended purpose and as required to reduce slipping, erosion or excess saturation. Fill intended to support buildings, structures, conduits, etc., shall be compacted in accordance with local requirements or
- 8. Topsoil is to be stripped and stockpiled in amounts necessary to complete finished grading of all exposed areas requiring topsoil. The stockpiled topsoil is to be located as designated on the plans. Topsoil shall not be placed while in a frozen or muddy condition, when the subgrade is excessively wet, or in a condition that may otherwise be detrimental to proper grading or proposed sodding or
- 9. Any and all fill material is to be free of brush, rubbish, timber, logs vegetative matter and stumps in amounts that will be detrimental to constructing stable fills. Maximum side slopes of exposed surfaces of earth to be 3:1 or as otherwise specified by local authorities.
- 10. Soil stabilization should be completed within 5 days of clearing or inactivity in construction.
- 11. Waste Materials All waste materials (including wastewater) shall be disposed of in accordance with local. state and federal law. Litter shall be picked up at the end of each work day.
- 12. The Contractor shall maintain on—site additional erosion control materials as a contingency in the event of a failure or when required to shore up existing BMPs. At a minimum, the on-site contingency materials should include 30 feet of silt fence and 5 straw haybales with 10 stakes.

Silt Sack - Type B




SOURCE: U.S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE, STORRS, CONNECTICUT

GEOTEXTILE SILT FENCE (GSF) NOT TO SCALE



ANTI-TRACKING EXIT PAD DETAIL (CE)



NOTE: MAY BE USED AS ALTERNATIVE TO GEOTEXTILE SILT FENCE. PERIMETER SEDIMENT BARRIER

CHECKLIST FOR EROSION CONTROL PLAN

PROJECT: Sonny's Place Bumper Boat & Mini-Golf Expansion

LOCATION: 349 Main Street, Somers, CT

MAINTENANCE OF MEASURES:

Project Dates:

PROJECT DESCRIPTION: Addition of Bumper Boats, Mini-Golf & Parking

RESPONSIBLE PERSONNEL: Jonathan Murray (860) 808-6047

PARCEL AREA: 25± acres

EROSION AND SEDIMENT CONTROL PLAN PREPARER: J.R. Russo & Associates, LLC

CHECKLIST:

Install construction entrance plan. Install perimeter As shown on sediment barriers plan. Install inlet As structures protection are installed.	Work Description Erosion & Sediment Control Measures	Location	Date Installed	Initials	Date Removed	Initials
entrance plan. Install perimeter As shown on sediment barriers plan. Install inlet As structures						
sediment barriers plan. Install inlet As structures						

Description or Number Date

This project is located at Sonny's Place, 349 Main Street in Somers. The proposed activity is the construction of an 18—hole miniature golf course, bumper boats and parking lot expansion. The suggested schedule of construction is as follows:

PROJECT NARRATIVE AND CONSTRUCTION SEQUENCE

1. Install construction anti-tracking pad (CE).

Date of groundbreaking for project:

Date of final stabilization:

- Install sediment barriers (GSF) at project perimeters.
- Demolish and temporarily relocation existing features to be removed per demolition plan. Strip topsoil. Stockpile suitable amount of topsoil for reuse on—site in areas shown.
- Stockpiles shall be surrounded by sediment barriers (GSF). Rough grade site.
- Install relocated gravel access road.
- Begin construction of golf course and bumper boats. Reconstruct swale along property line.
- Box out for parking lot.
- Install stormwater system.
- 0. Install parking lot base. Install concrete sidewalks.
- 12. Pave binder course. 13. Stabilize remaining areas to receive topsoil and permanently seed as soon as possible.
- 15. Install pavement top course in all areas. Sweep binder course and apply tack coat prior to
- placing pavement top course.
- 16. Apply paint striping. 17. Remove sediment barriers after site is fully stabilized.

Construction of this site is anticipated to begin in the summer of 2021, pending approvals. Temporary erosion control measures shall be installed prior to any soil disturbance and maintained throughout construction until soils have been stabilized with permanent vegetation.

The Contractor shall keep the area of disturbance to a minimum and establish vegetative cover on exposed soils as soon as practical. All soil and erosion control measures shall be installed and maintained in accordance with these plans and the "Connecticut DEP Guidelines for Soil Erosion and Sediment Control", as amended. The Contractor shall verify all conditions noted on the plans and shall immediately notify the Engineer of any discrepancies.

The developer shall be responsible for the repair/replacement/maintenance of all erosion control measures until all disturbed areas are stabilized. Accumulated sediment shall be removed as required to keep silt fence functional. In all cases, deposits shall be removed when the accumulated sediment has reached one—half above the ground height of the silt fence. This material is to be spread and stabilized in areas not subject to erosion, or to be used in areas which are not to be paved or built on. Silt fence (GSF) is to be replaced as necessary to maintain proper filtering action. Silt fence (qsf) are to remain in place and shall be maintained to insure efficient sediment capture until all areas above the erosion checks are stabilized and vegetation has been established.

Initials



REVISIONS BY: CJC CHK: TAC/JEU

Erosion Control Notes & Details

<u>DATE</u>

9-29-21 <u>SCALE</u> Not to Scale JOB NUMBER 2007-081 7 of 9

CB GRATE INLET PROTECTION (SILT SACK)

NOTE:
SILT SACK SHALL BE SIZED TO FIT EACH INLET GRATE (SINGLE OR


CONTRIBUTING WATERSHED IS STABILIZED WITH VEGETATION AND/OR

DOUBLE) AND SHALL BE CLEANED AND MAINTAINED UNTIL THE

SIZE L " X W " X D "


COMPACTED PROCESSED STONE BASE.

NOT TO SCALE



NOTE: WHERE SUBGRADES ARE ON WET SILT OR CLAY, CONTRACTOR TO INSTALL ADDITIONAL 12" OF 34" CRUSHED STONE ON TENSAR TRIAX GEOGRID BELOW GRAVEL


PAVEMENT DETAIL NOT TO SCALE



BITUMINOUS CONCRETE LIP CURBING


NOT TO SCALE

GRAVEL DRIVE DETAIL




NOTE: EXPANSION JOINTS TO BE PLACED BETWEEN ADJACENT SLABS, AT BUILDING LINE, AT CURBS, OR AT PENETRATING STRUCTURES.

TYPICAL SIDEWALK DETAIL NOT TO SCALE



PRECAST CONCRETE MANHOLE


NOT TO SCALE



NOTE: MODIFIED RIPRAP APRON (12" THICK) ON 6" GRANULAR BASE (M.02.01) ON MIRAFI 140N FABRIC OR EQUAL

TYPE A RIPRAP APRON (OP)

N.T.S.



 MINIMUM COVER OVER TOP OF PIPE SHALL BE 2'-0".
 WALL THICKNESS SHALL BE SUFFICIENT TO MEET HS 20 LOADING. 3. WALL THICKNESS FOR STRUCTURES OVER 10' HIGH IS 12" FOR CONCRETE BLOCK UNITS, INSIDE DIMENSIONS REMAIN THE SAME.
4. ALL PIPES SHALL BE CUT FLUSH WITH INSIDE WALLS.

5. ALL BRICKS SHALL BE CONCRETE.

TYPE "C" CATCH BASIN NOT TO SCALE

PRECAST CONCRETE UNIT ADJUST ELEVATION - W/CONC. BLOCKS OR BRICKS, 6" TO 12" ALL JOINTS TO BE POINTED -FLUSH & FULL PRECAST CONCRETE OR - CONCRETE MASONRY (MASONRY PRECAST SUMP OR SLAB (OR EQUAL) 3500 PSI 6" OF 3/4" CRUSHED 4'-4"

FRONT ELEVATION

SIDE ELEVATION

 MINIMUM COVER OVER TOP OF PIPE SHALL BE 1'-0".
 WALL THICKNESS SHALL BE SUFFICIENT TO MEET HS 20 LOADING. 3. WALL THICKNESS FOR STRUCTURES OVER 10' HIGH IS 12" FOR

CONCRETE BLOCK UNITS, INSIDE DIMENSIONS REMAIN THE SAME.

4. ALL PIPES SHALL BE CUT FLUSH WITH INSIDE WALLS.

5. ALL BRICKS SHALL BE CONCRETE.


TYPE "CL" CATCH BASIN NOT TO SCALE


REVISIONS BY: LF/TAC CHK: JEU

> 190 Place– Rte. 190 Sonny's349 Main Stree Somers, Co


Details

<u>DATE</u> 9-29-21 <u>SCALE</u> AS SHOWN JOB NUMBER 2007-081 <u>SHEET</u> 8 of 9







NOT TO SCALE




NOT TO SCALE









TREE PLANTING NOT TO SCALE



SHRUB PLANTING NOT TO SCALE



TOP OF BASIN ELEV.=195.0 ----4" COMPACTED GRAVEL -MIRAFI 500-X FABRIC 10' RIPRAP SPILLWAY NOT TO SCALE



STONE FILTER BERM NOT TO SCALE

Details

<u>DATE</u> 9-29-21 <u>SCALE</u> AS SHOWN JOB NUMBER 2007-081

REVISIONS BY: LF/TAC CHK: JEU

Place- Rte. 190 necticut Sonny's 349 Main Street Somers, Conr

SHEET 9 of 9