

**Tennis/Basketball Court RFP**  
**Questions and Answers**  
**June 07, 2010**

**Is a bid bond required? If so, in what percent?**

We did not require a bid bond in the bid package.

**Please confirm that testing is to be paid for and conducted by the contractor.**

Yes testing is to be paid for by the contractor and conducted by an outside engineering firm hired by the contractor.

**Please confirm that the fence around the basketball court is to remain (not being replaced).**

Yes, the basketball court fence is to remain.

**Please confirm that the new fence around the tennis court is schedule 40.**

Yes, the new fence around the tennis court is to be schedule 40.

**Please clarify the new fence requirements at the tennis courts. Is the fence replaced around the existing practice wall?**

Not around three existing practice walls but yes, at the common wall of the tennis and practice courts.

\*Correction:

Under Fencing: "The fence system will consist of 662LF of 10 foot high, black vinyl-coated steel fence..."

Should read: "The fence system will consist of 672LF of 10 foot high, black vinyl-coated steel fence..."

The tennis courts measure 124' x 212' at the fence.

Total lineal feet of new fence is 672.

**Is any work required inside the practice wall enclosure (crack repair, painting...)?**

Not at this time.

**Based on the documents, there may be a finish grade differential between the new tennis courts and the existing practice wall enclosure surface. Please confirm.**

Yes, the new surface shall be "feathered" down to the practice court surface.

**Please advise the new colors for the BB court and Tennis courts.  
Tennis is currently green & purple.**

Purple for the court area and green for the surrounding fields.

**Please confirm the acceptable daily work hours for the project.**

7:00 am – 5:00 pm Monday thru Friday excluding holidays. Weekend work will need to be authorized by the Town.